

GOVERNMENT OF INDIA

MINISTRY OF ROAD TRANSPORT AND HIGHWAYS (MoRTH) / NHAI

NATIONAL COMPETITIVE BIDDING: EPC OF 4-LANE GREENFIELD HIGHWAY BYPASS (28.4 KM / 113.6 LANE-KM)

Tender Reference: MoRTH/NHAI/EXP/2024/402 | Estimated Cost: INR 72.13 Crore | Evaluation: QCBS (70:30 Quality-to-Cost)

SECTION III (SCC) — STATUTORY ELIGIBILITY & HIGHWAY QUALITY BENCHMARKS

Bids are scrutinized strictly under GFR 2017 Rule 173 and IRC:37-2018 / IRC:SP:84-2019 standards to prevent premature pavement degradation and monsoon washouts.

Clause Ref	Highway Technical Parameter	Threshold Benchmark Condition	Mandatory?	Weight
SCC 2.1	Civil Highway Turnover	Minimum INR 25.00 Crore average in last 3 FY certified by CA with valid ICAI UDIN.	YES	15%
SCC 3.1	Past 4-Lane EPC Experience	Minimum 5.0 years with at least 1 completed 4-lane highway contract >= 2.0 km.	YES	20%
MoRTH 500	Sensor Paver Machinery	Ownership of minimum 2 Electronic Sensor Pavers (9m width) & 1 Slipform Concrete Paver.	YES	20%
HSE 7.2	Road Safety & ISO 45001	Active ISO 45001:2018 and ISO 9001:2015 safety accreditation on bid opening date.	YES	15%
ITB 8.2	EMD / Bid Security	INR 50,00,000 via irrevocable Bank Guarantee valid for 180 days.	YES	10%
EPC 17.1	5-Year Defect Liability (DLP)	Notarized guarantee for 60 months Defect Liability Period backed by 5% Performance Security.	YES	20%

SECTION VI — BILL OF QUANTITIES (BoQ) HIGHWAY SCHEDULE OF RATES

Engineering baseline unit rates derived from MoRTH Standard Data Book & IRC:37 Pavement Design for 150 MSA traffic load:

Item Code	Highway Work Item Description	Unit	Est. Qty	Est. Rate (INR)	Total Estimated (INR)
BOQ-HW-01	Earthwork excavation, embankment formation & subgrade CBR >= 8% 8.5%	Cum	2,50,000	280.00	7,00,00,000
BOQ-HW-02	Dense Bituminous Macadam (DBM) with VG-40 Bitumen (75mm)	Cum	45,000	8,500.00	38,25,00,000
BOQ-HW-03	Bituminous Concrete (BC) wearing course (Polymer Modified CRMB CRMB)	Cum	24,000	11,200.00	26,88,00,000
TOTAL	Total Estimated Project Value (DPR Baseline)				72,13,00,000